



DRAFT LOCATION PLAN

DONOVAN PARK_ MODULAR PUMP TRACK

ISSUE V1_12 SEPTEMBER 2023_1:200 @ A3



park—lifeTM

CONTACT 029 534 8859 INFO@PARKLIFE.CO.NZ PARKLIFE.CO.NZ

NOTE
The following details are a guide only.

The client/asset owner is responsible for providing a base-track under the Modular Pump Track that considers the following:

- Location
- Soil conditions
- Drainage
- Operational requirements
- Estimated period of install.

Following stripping of topsoil, insitu ground to be sighted and tested via Penetrometer Testing to min. 200KPa by a Geo-technical Engineer before placing basecourse.

Basecourse to be sighted and tested to minimum Clegg Impact Value (CIV) 20 by a Geo-technical Engineer before placing asphalt, concrete or Modular Pump Track on top.

Base-track only crossfall out 1%.

Maximum overall site fall 3%.

